



- CONT. ALUM. BASE MEMBER, MILL FINISH
- CONT. RUBBER INSERT
- 0.060 ALUM. CENTER PLATE, CLEAR ANODIZED FINISH
- 1 OR 2-HOUR FIRE BARRIER PER UL TEST REPORT
- FASTENERS @ 20" O.C. MAX, BY INSTALLER
- CLIPS (FIELD INSTALLED)
- CONT. ALUM. EXPOSED EXTRUSION, CLEAR ANODIZED FINISH

NOTE: 1 HOUR CONSTRUCTION INDICATED
 2 LAYERS OF GYPSUM BOARD FOR 2 HOUR CONSTRUCTION

SCALE: 6"=1'-0"



M.H. POWELL & CO., INC.
 ARCHITECTURAL SEISMIC EXPANSION JOINT SYSTEMS

2313 YATES AVENUE | PHONE : (323) 887-0037
 COMMERCE, CA 90040 | FAX : (323) 887-0877
 WEB : www.mhpowell.net

MODEL
KH-2-2

INTERIOR WALLS / CEILINGS
 Surface Mount

PROJECT : _____ PROJECT # : _____
 LOCATION : _____ DATE : _____
 ARCHITECT : _____
 CUSTOMER : _____

PAGE #