



1 OR 2-HOUR FIRE BARRIER
PER UL TEST REPORT

3"

3/8"

2 1/4"

7 1/2"

CONT. ALUM. BASE MEMBER, MILL FINISH

CONT. RUBBER INSERT

0.060 ALUM. CENTER PLATE, CLEAR ANODIZED FINISH

FASTENERS @ 20" O.C. MAX, BY INSTALLER

CLIPS (FIELD INSTALLED)

CONT. ALUM. EXPOSED EXTRUSION, CLEAR ANODIZED FINISH

NOTE: 1 HOUR CONSTRUCTION INDICATED
2 LAYERS OF GYPSUM BOARD FOR 2 HOUR CONSTRUCTION

SCALE: 6"=1'-0"



M.H. POWELL & CO., INC.
ARCHITECTURAL SEISMIC EXPANSION JOINT SYSTEMS

2313 YATES AVENUE | PHONE : (323) 887-0037
COMMERCE, CA 90040 | FAX : (323) 887-0877
WEB : www.mhpowell.net

MODEL
KH-3-2

INTERIOR WALLS / CEILINGS
Surface Mount

PROJECT : _____ PROJECT # : _____
LOCATION : _____ DATE : _____
ARCHITECT : _____
CUSTOMER : _____

PAGE #