



FASTENERS @ 20" O.C. MAX, BY INSTALLER

CONT. RUBBER INSERT

0.060 ALUM. CENTER PLATE, CLEAR ANODIZED FINISH

1 OR 2-HR FIRE BARRIER  
PER UL TEST REPORT

4"

8 1/2"

CONT. ALUM. BASE MEMBER, MILL FINISH

CLIPS (FIELD INSTALLED)

CONT. ALUM. EXPOSED EXTRUSION, CLEAR ANODIZED FINISH

SCALE: 6"=1'-0"



**M.H. POWELL & CO., INC.**  
ARCHITECTURAL SEISMIC EXPANSION JOINT SYSTEMS

2313 YATES AVENUE | PHONE : (323) 887-0037  
COMMERCE, CA 90040 | FAX : (323) 887-0877  
WEB : www.mhpowell.net

**MODEL**  
**KH-4-2**

INTERIOR WALLS / CEILINGS  
Flush Mount

PROJECT : \_\_\_\_\_ PROJECT # : \_\_\_\_\_  
LOCATION : \_\_\_\_\_ DATE : \_\_\_\_\_  
ARCHITECT : \_\_\_\_\_  
CUSTOMER : \_\_\_\_\_

PAGE #